

NOTES:

- 1-MATERIALS:
- HELIX PLATE PER CSA G40.21 50W, MIN.FY=60 KSI, ULTIMATE STRENGTH 70 KSI
- -TUBE PER ASTM A500 GR C, FY=60KSI, FU=70KSI
- 2-ANY CHANGE OF MATERIAL IS SUBJECT TO GOLIATHTECH APPROVAL
- 3-WELD PERFORMED IN ACCORDANCE WITH CSA STANDARD W47.1 AND GOLIATHTECH WELDING PROCEDURES. WELDERS ARE ALSO CERTIFIED TO THE AWS STANDARD.
- 4-HOT-DIP GALVANIZED, PARTS PER ASTM A123.

1

3		
2		
1	INITIAL RELEASE	2023-07-27
REV	MODIFICATION	DATE

GOLIAŢHITECH

GOLIATHTECH PRESTIGE LINE

TITLE: 10 Foot Screw Pile of 2 3/8 (0.154 wall) with a 13" Helix

EAL:	DWG. NO :
	GTPI23813-10FT
	DRAWN BY:
	R.E
	DESIGN BY:
	GOLIATHTECH
	CHECK BY:
	CPOC
	APP BY:
	CPOC
	OTHER NO:

FORMAT : A		REV.:	DATE :	PAGE :			
SCALE: N	TS	1	2023-07-27	1 DE			
THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION AND MAY NOT BE REPRODUCED OR COPIED							

WITHOUT THE EXPRESS WRITTEN PERMISSION OF A DULY AUTHORIZED REPRESENTATIVE OF GOLIATHTECH INC.

ı		Dimension (inches)	Description	MECHANICAL ASD LOAD CAPACITY							
	NO.			Undraced Shaft Ital	Compression (kips)		Tension	Lateral	Bending	Max Soil Capacity	
					0 Coupler	1 Coupler	2 Coupler	(kips)	(kips)	Moment (kips.ft)	Comp/Ten * (kips)
l	Α	120		0	33.4	33.4	33.4			0 1.93	15.75
l	В	13		5	12.4	6.7	4.0				
l	С	4 1/4		10	5.5	4.0	2.8	15.57	8.20		
l	D	PITCH 3		15	2.8	2.4	1.9				
l	Ε	3/8		20	1.8	1.6	1.3				
I	F	1		Note: 1. Soil capacity (P4) must be determined per Section 4.1.5 of this report.							·
I	G	1 1/2		Soli capacity (F4) must be determined per Section 4.1.3 or this report. Maximum ultimate soil capacity is determined from Pult = Kt x T based on the corresport.						e corresponding	

- 2. Maximum ultimate soil capacity is determined from Pult = Kt x T based on the corresponding maximum installation torque rating for the specific pile model. Allowable soil capacity is determined from Pa = Pult /2.0 based on the corresponding maximum installation torque rating for the specific pile model. See Section 4.1.5 for additional information.
- 3. Mechanical torsion rating is the maximum torsional resistance of the steel shaft.
- 4. Maximum Torque Per Soil Tests is the maximum torque achieved during field axial verification testing that was conducted to verify the pile axial capacity related to pile-soil interaction.
- 5. Maximum Installation Torque rating is the lower of the "mechanical torsion rating" and the "maximum torque per soil tests".
- 6. The allowable soil capacity under the IRC must be determined in accordance with Equation 3 of Section 4.1.5 of this report, when applicable.
- *7. Min required installation depth for tension is 12D where D is the diameter of the uppermost helix.
- 8. Max Soil Capacities based on the the tube torsional cpacity.

2 3/8

9/16

1/4

Weld

В