

## NOTES:

- 1-MATERIALS:
- HELIX PLATE PER CSA G40.21 50W, MIN.FY=60 KSI, ULTIMATE STRENGTH 70 KSI
- -TUBE PER ASTM A500 GR C, FY=60KSI, FU=70KSI
- 2-ANY CHANGE OF MATERIAL IS SUBJECT TO GOLIATHTECH APPROVAL
- 3-WELD PERFORMED IN ACCORDANCE WITH CSA STANDARD W47.1 AND GOLIATHTECH WELDING PROCEDURES. WELDERS ARE ALSO CERTIFIED TO THE AWS STANDARD.
- 4-HOT-DIP GALVANIZED, PARTS PER ASTM A123.

1

3		
2		
1	INITIAL RELEASE	2023-07-27
REV	MODIFICATION	DATE

## GOLIATH TECH

## **GOLIATHTECH PRESTIGE LINE**

TITLE: 4.5 Foot Screw Pile of 2 3/8 (0.154 wall) with a 15" Helix

	·
SEAL:	DWG. NO:
	GTPI23815-4.5FT
	DRAWN BY:
	R.E
	DESIGN BY:
	GOLIATHTECH
	CHECK BY:
	CPOC
	APP BY:
	CPOC
	OTHER NO:
	-

	FORMAT : A		REV.:	DATE:	PAGE:		
	SCALE :	NTS	1	2023-07-27	1 DE		
THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION AND MAY NOT BE REPRODUCED OR CORIED							

WITHOUT THE EXPRESS WRITTEN PERMISSION OF A DULY AUTHORIZED REPRESENTATIVE OF GOLIATHTECH INC.

ı		Dimension (inches)	Description	WECHANICAL ASD LOAD CAPACITY							
l	NO.			that't Hill	Compression		Tanaian	Leteval	Bending	Max Soil	
	NO.			Undraged shaft Luftal	0 Coupler	(kips) 1 Coupler	2 Coupler	Tension (kips)	(kips)	Moment (kips.ft)	Capacity Comp/Ten * (kips)
l	Α	54		0	33.4	33.4	33.4			1.93	15.75
l	В	15		5	12.4	6.7	4.0				
l	С	4 1/4		10	5.5	4.0	2.8	15.57	8.20		
l	D	PITCH 3		15	2.8	2.4	1.9				
l	Ε	3/8		20	1.8	1.6	1.3				
١	F	1		Note:	(D4) mu	at he dete	rminod n	or Section 4	1.5 of this r	oport	
۱	G	1 1/2		<ul> <li>1. Soil capacity (P4) must be determined per Section 4.1.5 of this report.</li> <li>2. Maximum ultimate soil capacity is determined from Pult = Kt x T based on the corresponding</li> </ul>							

- 2. Maximum ultimate soil capacity is determined from Pult = Kt x T based on the corresponding maximum installation torque rating for the specific pile model. Allowable soil capacity is determined from Pa = Pult /2.0 based on the corresponding maximum installation torque rating for the specific pile model. See Section 4.1.5 for additional information.

MECHANICAL ASD LOAD CADACITY

- 3. Mechanical torsion rating is the maximum torsional resistance of the steel shaft.
- 4. Maximum Torque Per Soil Tests is the maximum torque achieved during field axial verification testing that was conducted to verify the pile axial capacity related to pile-soil interaction.
- 5. Maximum Installation Torque rating is the lower of the "mechanical torsion rating" and the "maximum torque per soil tests".
- 6. The allowable soil capacity under the IRC must be determined in accordance with Equation 3 of Section 4.1.5 of this report, when applicable.
- \*7. Min required installation depth for tension is 12D where D is the diameter of the uppermost
- 8. Max Soil Capacities based on the tube torsional cpacity.

2 3/8

9/16

1/4

Weld