

Compression

(kips)

Coupler

62.7

15.0

9.8

6.0

4.0

Coupler

62.7

28.1

14.1

7.4

4.6

NO.	TES
-----	-----

- 1-MATERIALS:
- HELIX PLATE PER CSA G40.21 50W, MIN.FY=60 KSI, ULTIMATE STRENGTH 70 KSI
- -TUBE PER ASTM A500 GR C, FY=60KSI, FU=70KSI
- 2-ANY CHANGE OF MATERIAL IS SUBJECT TO GOLIATHTECH APPROVAL
- 3-WELD PERFORMED IN ACCORDANCE WITH CSA STANDARD W47.1
 AND GOLIATHTECH WELDING PROCEDURES. WELDERS ARE ALSO
 CERTIFIED TO THE AWS STANDARD.
- 4-HOT-DIP GALVANIZED, PARTS PER ASTM A123.

1

3		
2		
1	INITIAL RELEASE	2023-08-03
REV	MODIFICATION	DATE

Capacity Comp/Ten * (kips) 34.88 TITLE: 14

Max Soil

Bending

Moment

(kips.ft)

4.59

Note:

0

5

10

15

20

В

Dimension

(inches)

168

9

1

4 1/4

PITCH 3

3/8

1 1/2

2 7/8

9/16

1/4

Weld

Description

NO.

Α

В

C

D

Ε

F

G

1. Soil capacity (P4) must be determined per Section 4.1.5 of this report.

2

Coupler

62.7

8.1

6.3

4.5

3.3

2. Maximum ultimate soil capacity is determined from Pult = Kt x T based on the corresponding maximum installation torque rating for the specific pile model. Allowable soil capacity is determined from Pa = Pult /2.0 based on the corresponding maximum installation torque rating for the specific pile model. See Section 4.1.5 for additional information.

MECHANICAL ASD LOAD CAPACITY

Tension

(kips)

25.78

Lateral

(kips)

16.70

- 3. Mechanical torsion rating is the maximum torsional resistance of the steel shaft.
- 4. Maximum Torque Per Soil Tests is the maximum torque achieved during field axial verification testing that was conducted to verify the pile axial capacity related to pile-soil interaction.
- Maximum Installation Torque rating is the lower of the "mechanical torsion rating" and the "maximum torque per soil tests".
- 6. The allowable soil capacity under the IRC must be determined in accordance with Equation 3 of Section 4.1.5 of this report, when applicable.
- *7. Min required installation depth for tension is 12D where D is the diameter of the uppermost helix.
- 8. Max Soil Capacities based on the tube torsional cpacity.

GOLIATHTECH

GOLIATHTECH PRESTIGE LINE

TITLE: 14 Foot Screw Pile of 2 7/8 (0.250 wall) with a 09" Helix

DWG. NO:
GTP127809-14FT

DRAWN BY:
R.E

DESIGN BY:
GOLIATHTECH

CHECK BY:
CPOC

APP BY:
CPOC

OTHER NO:

FORMAT:	: A	REV.:	DATE :	PAGE:		
SCALE:	NTS	1	2023-08-03	1 DE		
THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION AND MAY NOT BE REPRODUCED OR COPIED						

WITHOUT THE EXPRESS WRITTEN PERMISSION OF A DULY AUTHORIZED REPRESENTATIVE OF GOLIATHTECH INC.