

NOTES:

- 1-MATERIALS:
- -PLATE PER CSA G40.21 50W, MIN.FY=60 KSI, ULTIMATE STRENGTH
- -TUBE PER ASTM A500 GR C, FY=60KSI, FU=70KSI
- 2-ANY CHANGE OF MATERIAL IS SUBJECT TO GOLIATHTECH APPROVAL
- 3-WELD PERFORMED IN ACCORDANCE WITH CSA STANDARD W47.1
 AND GOLIATHTECH WELDING PROCEDURES. WELDERS ARE ALSO
 CERTIFIED TO THE AWS STANDARD.
- 4-HOT-DIP GALVANIZED, PARTS PER ASTM A123.

3		
2		
1	INITIAL RELEASE	2023-05-23
REV	MODIFICATION	DATE

GOLIAŢHTECH

GOLIATHTECH PRESTIGE LINE

TITLE: Screw Pile of 2 7/8 (0.250 wall) with a 09" Helix

SEAL:	DWG. NO :
	GTPI27809
	DRAWN BY:
	R.E
	DESIGN BY:
	GOLIATHTECH
	CHECK BY:
	CPOC
	APP BY:
	CPOC
	OTHER NO:

FORMAT : A	REV.:	DATE :	PAGE:
SCALE: NTS	1	2023-05-23	1 DE

THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION AND MAY NOT BE REPRODUCED OR COPIED WITHOUT THE EXPRESS WRITTEN PERMISSION OF A DULY AUTHORIZED REPRESENTATIVE OF GOLIATHTECH INC.

			MECHANICAL ASD LOAD CAPACITY							
NO. Dimension		Description	Jun Length Line	Compression (kips)			Tension	Lateral	Bending	Max Soil Capacity
	(inches)		Unbrace Length,	0 Coupler	1 Coupler	2 Coupler	(kips)	(kips)	(kips.ft)	Comp/Ten * (kips)
Α	84		0	62.7	62.7	62.7				
В	9		5	28.1	15.0	8.1				
С	4 1/4		10	14.1	9.8	6.3	25.80	16.70	4.59	34.88
D	PITCH 3		15	7.4	6.0	4.5				
Ε	3/8		20	4.6	4.0	3.3				
F	1		Note:	(D4) mus	t ha data	rminad n	or Costion 4	1 E of this r	onort	
G	1 1/2		 Soil capacity (P4) must be determined per Section 4.1.5 of this report. Maximum ultimate soil capacity is determined from Pult = Kt x T based on the corresponding 							

- 2. Maximum ultimate soil capacity is determined from Pult = Kt x T based on the corresponding maximum installation torque rating for the specific pile model. Allowable soil capacity is determined from Pa = Pult /2.0 based on the corresponding maximum installation torque rating for the specific pile model. See Section 4.1.5 for additional information.
- 3. Mechanical torsion rating is the maximum torsional resistance of the steel shaft.
- 4. Maximum Torque Per Soil Tests is the maximum torque achieved during field axial verification testing that was conducted to verify the pile axial capacity related to pile-soil interaction.
- 5. Maximum Installation Torque rating is the lower of the "mechanical torsion rating" and the "maximum torque per soil tests".
- 6. The allowable soil capacity under the IRC must be determined in accordance with Equation 3 of Section 4.1.5 of this report, when applicable.
- *7. Min required installation depth for tension is 12D where D is the diameter of the uppermost helix.
- 8. Max Soil Capacities based on the the tube torsional cpacity.

2 7/8

9/16

1/4

Weld