

NOTES:

- 1-MATERIALS:
- HELIX PLATE PER CSA G40.21 50W, MIN.FY=60 KSI, ULTIMATE STRENGTH 70 KSI
- -TUBE PER ASTM A500 GR C, FY=60KSI, FU=70KSI
- 2-ANY CHANGE OF MATERIAL IS SUBJECT TO GOLIATHTECH APPROVAL
- 3-WELD PERFORMED IN ACCORDANCE WITH CSA STANDARD W47.1 AND GOLIATHTECH WELDING PROCEDURES. WELDERS ARE ALSO CERTIFIED TO THE AWS STANDARD.
- 4-HOT-DIP GALVANIZED, PARTS PER ASTM A123.

1

3		
2		
1	INITIAL RELEASE	2023-08-03
REV	MODIFICATION	DATE

Compression **Max Soil Dimension Bending** NO. Description (kips) Tension Lateral Capacity (inches) Moment (kips) 2 (kips) Comp/Ten (kips.ft) Coupler Coupler Coupler * (kips) Α 120 0 53.5 53.5 53.5 13 5 В 28.1 15.0 8.1 C 4 1/2 14.1 9.8 6.3 25.78 16.70 4.59 34.88 10 D PITCH 3 15 7.4 6.0 4.5 Ε 3/8 20 4.6 4.0 3.3

Note:

В

F

G

Н

1 1/2

2 7/8

9/16

Weld

1/4

- 1. Soil capacity (P4) must be determined per Section 4.1.5 of this report.
- 2. Maximum ultimate soil capacity is determined from Pult = Kt x T based on the corresponding maximum installation torque rating for the specific pile model. Allowable soil capacity is determined from Pa = Pult /2.0 based on the corresponding maximum installation torque rating for the specific pile model. See Section 4.1.5 for additional information.

MECHANICAL ASD LOAD CAPACITY

- 3. Mechanical torsion rating is the maximum torsional resistance of the steel shaft.
- 4. Maximum Torque Per Soil Tests is the maximum torque achieved during field axial verification testing that was conducted to verify the pile axial capacity related to pile-soil interaction.
- 5. Maximum Installation Torque rating is the lower of the "mechanical torsion rating" and the "maximum torque per soil tests".
- 6. The allowable soil capacity under the IRC must be determined in accordance with Equation 3 of Section 4.1.5 of this report, when applicable.
- *7. Min required installation depth for tension is 12D where D is the diameter of the uppermost
- 8. Max Soil Capacities based on the tube torsional cpacity.

 	_
	TECH

GOLIATHTECH PRESTIGE LINE

TITLE: 10 Foot Screw Pile of 2 7/8 (0.250 wall) with a 13" Helix

SEAL:	DWG. NO :
	GTPI27813-10FT
	DRAWN BY:
	R.E
	DESIGN BY:
	GOLIATHTECH
	CHECK BY:
	СРОС
	APP BY:
	CPOC
	OTHER NO:
	-

FORMAT : A		REV.:	DATE :	PAGE:			
SCALE:	NTS	1	2023-08-03	1 DE			
THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION AND MAY NOT BE REPRODUCED OR COPIED							

WITHOUT THE EXPRESS WRITTEN PERMISSION OF A DULY AUTHORIZED REPRESENTATIVE OF GOLIATHTECH INC.