

N	OT	ES
---	----	----

- 1-MATERIALS:
- -PLATE PER CSA G40.21 50W, MIN.FY=60 KSI, ULTIMATE STRENGTH
- -TUBE PER ASTM A500 GR C, FY=60KSI, FU=70KSI
- 2-ANY CHANGE OF MATERIAL IS SUBJECT TO GOLIATHTECH APPROVAL
- 3-WELD PERFORMED IN ACCORDANCE WITH CSA STANDARD W47.1
  AND GOLIATHTECH WELDING PROCEDURES. WELDERS ARE ALSO
  CERTIFIED TO THE AWS STANDARD.
- 4-HOT-DIP GALVANIZED, PARTS PER ASTM A123.

1

3		
2		
1	INITIAL RELEASE	2023-08-03
REV	MODIFICATION	DATE

## GOLIAŢHŒCH

## **GOLIATHTECH PRESTIGE LINE**

TITLE: 3.5 Foot Screw Pile of 2 7/8 (0.250 wall) with a 13" Helix

SEAL:	DWG. NO :
	GTPI27813-3.5FT
	DRAWN BY:
	R.E
	DESIGN BY:
	GOLIATHTECH
	CHECK BY:
	CPOC
	АРР ВҮ:
	CPOC
	OTHER NO:
	-

FORMAT : /	A	REV.:	DATE:	PAGE:	
SCALE :	NTS	1	2023-08-03	1 DE	
THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION AND MAY NOT BE PERPODICED OF CORED					

ITHIS DOCUMENT CONTAINS PROPRIETARY INFORMATION AND MAT NOT BE REPRODUCED OR COPIE
WITHOUT THE EXPRESS WRITTEN PERMISSION OF A DULY AUTHORIZED REPRESENTATIVE OF
GOLIATHTECH INC.

ı			Description	MECHANICAL ASD LOAD CAPACITY							
l	NO.	Dimension		Jubisced Staff, Luften	Compression (kips)		Tension	Lateral	Bending	Max Soil	
$\ $	140.	(inches)			0 Coupler	1	2 Coupler	(kips)	(kips)	Moment (kips.ft)	Capacity Comp/Ten * (kips)
l	Α	42		0	53.5	53.5	53.5	25.78	16.70	4.59 34	
l	В	13		5	28.1	15.0	8.1				34.88
I	С	4 1/4		10	14.1	9.8	6.3				
l	D	PITCH 3		15	7.4	6.0	4.5				
l	Е	3/8		20	4.6	4.0	3.3				
١	F	1		Note:	(D4) mu	at he dete	rminad n	or Section 4	1.5 of this r	conort	
۱	G	1 1/2		<ul> <li>1. Soil capacity (P4) must be determined per Section 4.1.5 of this report.</li> <li>2. Maximum ultimate soil capacity is determined from Pult = Kt x T based on the corresponding</li> </ul>					corresponding		

2. Maximum ultimate soil capacity is determined from Pult = Kt x T based on the corresponding maximum installation torque rating for the specific pile model. Allowable soil capacity is determined from Pa = Pult /2.0 based on the corresponding maximum installation torque rating for the specific pile model. See Section 4.1.5 for additional information.

MECHANICAL ACD LOAD CADACITY

- 3. Mechanical torsion rating is the maximum torsional resistance of the steel shaft.
- 4. Maximum Torque Per Soil Tests is the maximum torque achieved during field axial verification testing that was conducted to verify the pile axial capacity related to pile-soil interaction.
- 5. Maximum Installation Torque rating is the lower of the "mechanical torsion rating" and the "maximum torque per soil tests".
- 6. The allowable soil capacity under the IRC must be determined in accordance with Equation 3 of Section 4.1.5 of this report, when applicable.
- \*7. Min required installation depth for tension is 12D where D is the diameter of the uppermost helix.
- 8. Max Soil Capacities based on the tube torsional cpacity.

2 7/8

9/16

Weld

1/4