
2



NOTES:

- 1-MATERIALS:
- HELIX PLATE PER CSA G40.21 50W, MIN.FY=60 KSI, ULTIMATE STRENGTH 70 KSI
- -TUBES PER ASTM A500 GR C, FY=60KSI, FU=70KSI
- 2-ANY CHANGE OF MATERIAL IS SUBJECT TO GOLIATHTECH APPROVAL
- 3-WELD PERFORMED IN ACCORDANCE WITH CSA STANDARD W47.1 AND GOLIATHTECH WELDING PROCEDURES. WELDERS ARE ALSO CERTIFIED TO THE AWS STANDARD.
- 4-HOT-DIP GALVANIZED, PARTS PER ASTM A123.

3		
2		
1	INITIAL RELEASE	2023-09-20
REV		DATE

MECHANICAL ASD LOAD CAPACITY Max Soil Compression Bending Dimension NO. Description Tension l Lateral Capacity (kips) Moment (inches) Comp/Ten 2 (kips) (kips) (kips.ft) Coupler Coupler | Coupler * (kips) 168 0 70.6 70.6 70.6 9 5 40.2 26.2 16.3 В 4 1/4 10 22.8 17.5 12.5 C 28.78 21.30 7.12 43.75 15 D 3 PITCH 13.0 11.1 8.8 Ε 3/8 20 8.2 6.3 7.4 Note: F 1

- 1. Soil capacity (P4) must be determined per Section 4.1.5 of this report.
- 2. Maximum ultimate soil capacity is determined from Pult = Kt x T based on the corresponding maximum installation torque rating for the specific pile model. Allowable soil capacity is determined from Pa = Pult /2.0 based on the corresponding maximum installation torque rating for the specific pile model. See Section 4.1.5 for additional information.
- 3. Mechanical torsion rating is the maximum torsional resistance of the steel shaft.
- 4. Maximum Torque Per Soil Tests is the maximum torque achieved during field axial verification testing that was conducted to verify the pile axial capacity related to pile-soil interaction.
- 5. Maximum Installation Torque rating is the lower of the "mechanical torsion rating" and the "maximum torque per soil tests".
- 6. The allowable soil capacity under the IRC must be determined in accordance with Equation 3 of Section 4.1.5 of this report, when applicable.
- *7. Min required installation depth for tension is 12D where D is the diameter of the uppermost helix.
- 8. Max Soil Capacities based on the the tube torsional cpacity.

		TECH
	d- U U	

(-())	ΙΔΙΗ	1 F (H	PREST	1(-F I	INI

TITLE: 14' Triple Helix Screw Pile of 3 1/2 (0.250 wall) with a 9", 11" and 13" Helix

SEAL:	DWG. NO:
	GTPI312091113-14FT
	DRAWN BY:
	ARG
	DESIGN BY:
	GOLIATHTECH
	CHECK BY:
	CPOC
	APP BY:
	CPOC
	OTHER NO:
	[-

FORMAT : A	REV.:	DATE :	PAGE:
SCALE: NTS	1	2023-09-20	1 DE

THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION AND MAY NOT BE REPRODUCED OR COPIED WITHOUT THE EXPRESS WRITTEN PERMISSION OF A DULY AUTHORIZED REPRESENTATIVE OF GOLIATHTECH INC.

1 1/2

3 1/2

9/16

1/4

3/8

3/8

27

11

33

13

Weld

G

Н

J

M

N

0

Р

Α

В