

NOTES:

1-MATERIALS:

1

- HELIX PLATE PER CSA G40.21 50W, MIN.FY=60 KSI, ULTIMATE STRENGTH 70 KSI
- -TUBE PER ASTM A500 GR C, FY=60KSI, FU=70KSI

2-ANY CHANGE OF MATERIAL IS SUBJECT TO GOLIATHTECH APPROVAL 3-WELD PERFORMED IN ACCORDANCE WITH CSA STANDARD W47.1 AND GOLIATHTECH WELDING PROCEDURES. WELDERS ARE ALSO CERTIFIED TO THE AWS STANDARD.

В

3		
2		
1	INITIAL RELEASE	2023-07-31
REV	MODIFICATION	DATE

GOLIAŢHITECH

GOLIATHTECH VENTURA LINE

TITLE: 4.5 Foot Screw Pile of 2 7/8 (0.250 wall) with a 11" Helix

DWG. NO:
VGTPI27811-4.5FT

DRAWN BY:
R.E

DESIGN BY:
GOLIATHTECH
CHECK BY:
CPOC
APP BY:
CPOC
OTHER NO:

F	ORMAT:	Α	REV.:	DATE :	PAGE:
9	SCALE :	NTS	1	2023-07-31	1 DE
П	HIS DOCUME	NT CONTAIN	IS PROPRIETARY INFORMA	ATION AND MAY NOT BE REPRODUC	ED OR COPIED

HIS DOCUMENT CONTAINS PROPRIETARY INFORMATION AND MAY NOT BE REPRODUCED OR COPIL
WITHOUT THE EXPRESS WRITTEN PERMISSION OF A DULY AUTHORIZED REPRESENTATIVE OF
GOLIATHTECH INC.

	Dimension (inches)	Description	MECHANICAL ASD LOAD CAPACITY							
NO.			Unbraced Straft Lutto	Compression (kips)		Tension	Lateral	Bending	Max Soil Capacity	
				0 Coupler	1 Coupler	2 Coupler	(kips)	(kips)	Moment (kips.ft)	Comp/Ten * (kips)
Α	54		0	57.1	57.1	57.1	21.51	14.40	3.99	34.88
В	11		5	24.4	13.1	7.1				
С	4 1/4		10	12.2	8.5	5.5				
D	PITCH 3		15	6.5	5.3	3.9				
Е	3/8		20	4.0	3.5	2.9				
F	1		Note:	(D4) mus	at he dete	rminad n	or Section 4	1 5 of this r	oport	
G	1 1/2		Soil capacity (P4) must be determined per Section 4.1.5 of this report. Maximum ultimate soil capacity is determined from Pult = Kt x T based on the corresponding.							

2. Maximum ultimate soil capacity is determined from Pult = Kt x T based on the corresponding maximum installation torque rating for the specific pile model. Allowable soil capacity is determined from Pa = Pult /2.0 based on the corresponding maximum installation torque rating for the specific pile model. See Section 4.1.5 for additional information.

MECHANICAL ACDIOAD CADACITY

- 3. Mechanical torsion rating is the maximum torsional resistance of the steel shaft.
- 4. Maximum Torque Per Soil Tests is the maximum torque achieved during field axial verification testing that was conducted to verify the pile axial capacity related to pile-soil interaction.
- 5. Maximum Installation Torque rating is the lower of the "mechanical torsion rating" and the "maximum torque per soil tests".
- The allowable soil capacity under the IRC must be determined in accordance with Equation 3 of Section 4.1.5 of this report, when applicable.
- *7. Min required installation depth for tension is 12D where D is the diameter of the uppermost helix.

 8. Max Soil Capacities based on the the tube torsional cpacity.
- 2

2 7/8

9/16

1/4

Weld