

NOTES:

- 1-MATERIALS:
- HELIX PLATE PER CSA G40.21 50W, MIN.FY=60 KSI, ULTIMATE STRENGTH 70 KSI
- -TUBES PER ASTM A500 GR C, FY=60KSI, FU=70KSI

CERTIFIED TO THE AWS STANDARD.

1

2-ANY CHANGE OF MATERIAL IS SUBJECT TO GOLIATHTECH APPROVAL 3-WELD PERFORMED IN ACCORDANCE WITH CSA STANDARD W47.1 AND GOLIATHTECH WELDING PROCEDURES. WELDERS ARE ALSO

| 3 | | |
|-----|-----------------|------------|
| 2 | | |
| 1 | INITIAL RELEASE | 2023-09-20 |
| REV | MODIFICATION | DATE |

GOLIATH TECH

GOLIATHTECH VENTURA LINE

TITLE: Double Helix Screw Pile of 2 7/8 (0.250 wall) with a 15" and 17" Helix

SFAL:

DWG. NO: VGTPI2781517 DRAWN BY: ARG DESIGN BY: **GOLIATHTECH** CHECK BY: CPOC APP BY: CPOC OTHER NO:

| FORMAT : A | REV.: | DATE : | PAGE : | |
|------------|-------|------------|--------|--|
| SCALE: NTS | 1 | 2023-09-20 | 1 DE | |

THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION AND MAY NOT BE REPRODUCED OR COPIED WITHOUT THE EXPRESS WRITTEN PERMISSION OF A DULY AUTHORIZED REPRESENTATIVE OF GOLIATHTECH INC.

| | Dimension (inches) | Description | WIECHANICAL ASD LOAD CAI ACTT | | | | | | | |
|----|-----------------------|-------------|--|-----------------------|--------------|--------------|----------|---------|----------------------|-------------------|
| NO | | | d Shaft Lifts | Compression (kips) | | Tension | Lateral | Bending | Max Soil Capacity | |
| | | | Unbraced Shaft Luften | 0 Coupler | 1 Coupler | 2 Coupler | (kips) (| (kips) | Moment (kips.ft) | Comp/Ten * (kips) |
| Α | 84 | | 0 | 57.1 | 57.1 | 57.1 | | | | |
| В | 15 | | 5 | 24.4 | 13.1 | 7.1 | | | | |
| С | 4 1/4 | | 10 | 12.2 | 8.5 | 5.5 | 21.51 | 14.40 | 3.99 | 34.88 |
| D | 3 PITCH | | 15 | 6.5 | 5.3 | 3.9 | | | | |
| Е | 3/8 | | 20 | 4.0 | 3.5 | 2.9 | | | | |
| F | 1 | | Note: 1. Soil capacity (P4) must be determined per Section 4.1.5 of this report. | | | | | | | |
| | | | 1. Soil capacity (F4) must be determined per Section 4.1.3 of this report. | | | | | | | |

- 2. Maximum ultimate soil capacity is determined from Pult = Kt x T based on the corresponding maximum installation torque rating for the specific pile model. Allowable soil capacity is determined from Pa = Pult /2.0 based on the corresponding maximum installation torque rating for the specific pile model. See Section 4.1.5 for additional information.

MECHANICAL ASD LOAD CAPACITY

- 3. Mechanical torsion rating is the maximum torsional resistance of the steel shaft.
- 4. Maximum Torque Per Soil Tests is the maximum torque achieved during field axial verification testing that was conducted to verify the pile axial capacity related to pile-soil interaction.
- 5. Maximum Installation Torque rating is the lower of the "mechanical torsion rating" and the "maximum torque per soil tests".
- 6. The allowable soil capacity under the IRC must be determined in accordance with Equation 3 of Section 4.1.5 of this report, when applicable.
- *7. Min required installation depth for tension is 12D where D is the diameter of the uppermost
- 8. Max Soil Capacities based on the tube torsional cpacity.

G

Н

K

M

N

0

Р

1 1/2

2 7/8

9/16

Weld

Weld

1/4

3 PITCH

3/8

1/4

2 7/8

45

17