

## NOTES:

- 1-MATERIALS:
- HELIX PLATE PER CSA G40.21 50W, MIN.FY=60 KSI, ULTIMATE STRENGTH 70 KSI
- -TUBE PER ASTM A500 GR C, FY=60KSI, FU=70KSI

2-ANY CHANGE OF MATERIAL IS SUBJECT TO GOLIATHTECH APPROVAL 3-WELD PERFORMED IN ACCORDANCE WITH CSA STANDARD W47.1 AND GOLIATHTECH WELDING PROCEDURES. WELDERS ARE ALSO CERTIFIED TO THE AWS STANDARD.

3		
2		
1	INITIAL RELEASE	2023-07-31
REV	MODIFICATION	DATE

## GOLIATHTECH

## **GOLIATHTECH VENTURA LINE**

TITLE: 4.5 Foot Screw Pile of 2 7/8 (0.250 wall) with a 19" Helix

ς	F	Δ١	١.	
_	_,	•	٠.	

DWG. NO :
VGTPI27819-4.5FT
DRAWN BY:
R.E
DESIGN BY:
GOLIATHTECH
CHECK BY:
CPOC
APP BY:
CPOC
OTHER NO:
-

FORMAT : A SCALE : NTS	REV.:	DATE: 2023-07-31	PAGE: 1 DE
------------------------	-------	------------------	---------------

THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION AND MAY NOT BE REPRODUCED OR COPIED WITHOUT THE EXPRESS WRITTEN PERMISSION OF A DULY AUTHORIZED REPRESENTATIVE OF GOLIATHTECH INC.

			MECHANICAL ASD LOAD CAPACITY							
NO. Dimension		Description	d Straft Light	Compression (kips)			Tension	Lateral	Bending	Max Soil Capacity
	(inches)		Undraced Staff, Luften	0 Coupler	1 Coupler	2 Coupler	(kips)	(kips)	Moment (kips.ft)	Comp/Ten * (kips)
Α	54		0	57.1	57.1	57.1				
В	19		5	24.4	13.1	7.1				
С	4 1/4		10	12.2	8.5	5.5	21.51	14.40	3.99	34.88
D	PITCH 3		15	6.5	5.3	3.9				
Е	1/2		20	4.0	3.5	2.9				
F	1		Note: 1 Soil capacity	(P4) mus	t be dete	rmined p	er Section 4	1.5 of this re	eport	

- Soil capacity (P4) must be determined per Section 4.1.5 of this report.
- 2. Maximum ultimate soil capacity is determined from Pult = Kt x T based on the corresponding maximum installation torque rating for the specific pile model. Allowable soil capacity is determined from Pa = Pult /2.0 based on the corresponding maximum installation torque rating for the specific pile model. See Section 4.1.5 for additional information.

MECHANICAL ACD LOAD CADACITY

- 3. Mechanical torsion rating is the maximum torsional resistance of the steel shaft.
- 4. Maximum Torque Per Soil Tests is the maximum torque achieved during field axial verification testing that was conducted to verify the pile axial capacity related to pile-soil interaction.
- 5. Maximum Installation Torque rating is the lower of the "mechanical torsion rating" and the "maximum torque per soil tests".
- 6. The allowable soil capacity under the IRC must be determined in accordance with Equation 3 of Section 4.1.5 of this report, when applicable.
- \*7. Min required installation depth for tension is 12D where D is the diameter of the uppermost
- 8. Max Soil Capacities based on the tube torsional cpacity.

1 1/2

2 7/8

9/16

1/4

Weld