

В

3 1/2

9/16

1/4

Weld

N	OT	ES
---	----	----

1-MATERIALS:

-PLATE PER CSA G40.21 50W, MIN.FY=60 KSI, ULTIMATE STRENGTH 70 KSI

-TUBE PER ASTM A500 GR C, FY=60KSI, FU=70KSI

CERTIFIED TO THE AWS STANDARD.

1

2-ANY CHANGE OF MATERIAL IS SUBJECT TO GOLIATHTECH APPROVAL 3-WELD PERFORMED IN ACCORDANCE WITH CSA STANDARD W47.1 AND GOLIATHTECH WELDING PROCEDURES. WELDERS ARE ALSO

В

	3		
	2		
	1	INITIAL RELEASE	2023-08-04
	REV	MODIFICATION	DATE

## GOLIAŢHTECH

## **GOLIATHTECH VENTURA LINE**

TITLE: Screw Pile of 3 1/2 (0.250 wall) with a 11" Helix

SEAL:

DWG. NO:
VGTPI31211

DRAWN BY:
R.E

DESIGN BY:
GOLIATHTECH
CHECK BY:
CPOC
APP BY:
CPOC
OTHER NO:

	FORMAT : A SCALE : NTS	REV.:	DATE: 2023-08-04	PAGE: 1 DE		
THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION AND MAY NOT BE REPRODUCED OR COPI						

I'MIS DOCUMENT CONTAINS PROPRIETART INFORMATION AND MAT NOT BE REPRODUCED OR COPIE
WITHOUT THE EXPRESS WRITTEN PERMISSION OF A DULY AUTHORIZED REPRESENTATIVE OF
GOLIATHTECH INC.

ı				MECHANICAL ASD LOAD CAPACITY							
	NO.	Dimension (inches)	Description	d Shaft Luftel	Compression (kips)		Tension Latera	Lateral	Bending Moment	Max Soil Capacity	
		(inches)		Undraced Staft, Luften	0 Coupler	1 Coupler	2 Coupler	(kips)	(kips)	(kips.ft)	Comp/Ten * (kips)
l	Α	84		0	58.4	58.4	58.4	22.79	18.50	6.20	43.75
l	В	11		5	34.5	22.3	13.9				
l	С	4 1/4		10	19.6	14.9	10.6				
l	D	PITCH 3		15	11.3	9.5	7.5				
l	E	3/8		20	7.1	6.3	5.4				
١	F	1		Note:							
١	G	1 1/2		Soil capacity (P4) must be determined per Section 4.1.5 of this report.     Maximum ultimate soil capacity is determined from Pult = Kt x T based on the					e corresponding		

2. Maximum ultimate soil capacity is determined from Pult = Kt x T based on the corresponding maximum installation torque rating for the specific pile model. Allowable soil capacity is determined from Pa = Pult /2.0 based on the corresponding maximum installation torque rating for the specific pile model. See Section 4.1.5 for additional information.

MECHANICAL ASD LOAD CADACITY

- 3. Mechanical torsion rating is the maximum torsional resistance of the steel shaft.
- 4. Maximum Torque Per Soil Tests is the maximum torque achieved during field axial verification testing that was conducted to verify the pile axial capacity related to pile-soil interaction.
- 5. Maximum Installation Torque rating is the lower of the "mechanical torsion rating" and the "maximum torque per soil tests".
- 6. The allowable soil capacity under the IRC must be determined in accordance with Equation 3 of Section 4.1.5 of this report, when applicable.
- \*7. Min required installation depth for tension is 12D where D is the diameter of the uppermost helix.

  8. Max Soil Capacities based on the the tube torsional cpacity.